



Rajasthan Medical Services Corporation Limited, Jaipur
Gandhi Block, Swasthya Bhawan, Tiлак Marg, C-Scheme, Jaipur - 302005

Ph. No. 0141-2223887, Fax : 0141-2228065
CIN:U24232RJ2011ISGC035067

E-mail : edepmmisc-ri@nlc.in
Website: www.rmssc.nic.in

No.F-8 (117)RMSC/EPM/M-4/18-19/NIB-372/ 4195

Dated: 26-10-18

All Principal, Medical Colleges,
All the Superintendent of Medical College & Attached Hospitals.
Director (PH/HA/IEC/AIDS/RCH)

Sub:- The Rate Contract for the 25 KVA Silent Diesel Generator Set

Please find enclosed herewith approved firm and rates etc. in respect of item 25 KVA Silent Diesel Generator Set for the rate contract No 527ending on 31.10.2020 The Rate Contract and its terms & conditions are also available on Rajasthan Medical Services Corporation Ltd., Website www.rmssc.nic.in.

In reference to above Rate Contract No. F-8(117) RMSC/EPM/M-4/18-19/NIB-372/ Dated:the supplier has executed the agreement with RMSC, as enclose here for your information & necessary action.

No.F-8 (67)RMSC/EPM/M-4/18-19/NIB-372/

Dated:

Executive Director (EPM)
Rajasthan Medical Services Corporation Ltd, Jaipur

Copy forwarded to the following for information & necessary action:

1. PS to Hon'ble Health Minister, Medical & Health Deptt. Govt. of Rajasthan.
2. PS to PHS, Medical Health & FW Deptt. Rajasthan, Jaipur.
3. PA to Director, (PH)/(Aids)/(FW)/(RCH)/(IEC).
4. Project Director, NRHM.
5. Principal, Medical College, Ajmer, Bikaner, Jaipur, Jodhpur, Kota, Jhalawar & Udaipur.
6. Superintendent, SMS Hospital, Zenana Hospital, Mahila Chikitsalya, Mental Hospital, J.K. Lon Hospital, T.B & Chest Hospital, Jaipur.
7. Superintendent Associated Group of Hospital-Ajmer, M.G. Hospital, Jodhpur, Ummaid Hospital- Jodhpur, PBM Hospital-Bikaner, MBS Hospital-Kota & A.G. Hospital-Udaipur.
8. Director, Medical & Health Services (ESI), Mobile Surgical Unit, Raj. Jaipur.
9. Addl. Director, Medical & Health Services (PW)/(RH)/(Hospital Admn.)
10. Joint Director, Medical & Health Services, (Zone) Jaipur, Ajmer, Udaipur, Jodhpur, Bikaner, Kota & Bharatpur.
11. All Dy. CM&HO's.
12. AGM (IT), RMSC, Jaipur.
13. M/s Tanwar Industries, Jalupura Link Road, M.I. Road Jaipur-302001 Email-info@tanwarindustries.com
14. Guard file.

Executive Director (EPM)
Rajasthan Medical Services Corporation Ltd, Jaipur

Rajasthan Medical Services Corporation Limited, Jaipur

Gandhi Block, Swasthya Bhawan, Tilak Marg, C-Scheme, Jaipur - 302005

Ph. No. 0141-2223887, Fax : 0141-2228065

E-mail : edepmrm-sc-ri@nic.in

Website: www.health.rajasthan.gov.in

No. F-8(117) RMSC/EPM/M-4/2018-19/NIB-372/ 4196

Dated: 26-10-18

Order for Rate Contract

S. No.	Item	Detail
1.	Name of Equipment / Item	25 KVA SILENT DIESEL GENERATOR SET
2.	Name & Address of Firm	M/s Tanwar Industries, Jalupura Link Road, M. I. Road Jaipur Email: info@tanwarindustries.com
3.	Brand/ Model / Make	Mahindra Powerol
4.	Packing Unit	Each
5.	R/C No. & Validity	(R.C. No 527 /Valid upto 31-10-2020)
6.	Net Rate Per packing Unit (Rs.)	3,50,000.00 (Three Lac Fifty Thousand Only) HSN Code 85021100
8.	RMSC Surcharge @5%	Rs. 17,500.00
9.	Rates for Supply to RMSC from Suppliers	
	(i) Basic Rate (In Rs.)	3,50,000.00
	(ii) IGST @ 18 % (In Rs.)	63,000.00
	(iii) CGST @ 0 % (In Rs.)	0.00
	(iv) SGST @ 0 % (In Rs.)	0.00
	(v) Approved Rate for Suppliers From RMSC ((i)+(ii)+(iii)+(iv)) (In Rs.)	4,13,000.00

km



10.

Rate for Supply To Consignee From RMSC

(i)	Basic Rate (In Rs.)	3,50,000.00
(ii)	RMSC Surcharge @ 5% on (In Rs.)	17,500.00
(iii)	CGST @9% {On (i)+(ii)} (In Rs.)	33,075.00
(iv)	SGST @ 9% {On (i)+(ii)} (In Rs.)	33,075.00
(v)	Approved Rate for Consignee From RMSC {(i)+(ii)+(iii)+(iv)} (In Rs.)	4,33,650.00

11

Technical specifications of 25 KVA SILENT DIESEL GENERATOR SET

- A. Supply, Installation, Testing & Commissioning of Silent DG Set complete with 1500 RPM Diesel Engine of suitable BHP & AC Brush less SPI Alternator mounted on a common base Frame & coupled through a flexible coupling or close coupled. Alternator shall be self regulated w standard Alternator Protection (Over voltage, over speed & under voltage, under speed warning & shutdown). Engine shall have resident silencer, up to 3 M exhaust piping, electronic / Mechanical governor, Manual & electric Start, Batteries, Engine instruments panel, AVM and w Weatherproof, powder coated Acoustic enclosure for DG set for sound attenuation fabricated from 1.6 to 2.0 mm CRCA sheet steel (structu with side wall fabricated from 1.6 to 2.0 mm CRCA sheet & filled with 100mm thick glass wool (96Kg/m3)/Foam. as per IS 8183 the doors 100 mm thick and fabricated from 1.6mm CRCA sheet packed with acoustic material. All doors/ opening are sealed with neoprene/EPDM gask The enclosure has built in fuel tank, residential silencer with protection and tripping of DG set.
- B. Against temperature of more than 50 degree centigrade. All controls for operation of DG set are visible and accessible from outside t enclosure with DG control panel having Microprocessor based Genset monitoring & control system, MCCB, Ammeter, Voltmeter, PF met frequency meter, KWH meter, Ind.lamps etc. mounted inside enclosure. The enclosure should be suitable for following capacity DG sets a alternator. Noise level shall be less than 75 dBA at a distance of 1 Mtrs. duly certified by authorized agency etc. complete in all respect following capacity.
- C. A-Air Cooled & Naturally Aspirated/Radiator cooled/Turbo charged-
- D. 25 KVA at 0.8 pf 415V 50Hz 3-Ø
- E. SITC of Auto main failure (AMF) Panel fabricated from CRCA sheet steel 1.6 to 2 mm Thick , Powder coated finish , Engine Start & St commands, control Relays , selector switches based or composite multifunction meter for Ammeter & Voltmeter, Control & Power Contacto Timers, Electronic Hooter , Visual & Alarm indication for faults, UPS, operator interface panel complete in all respect suitable for followi capacity/ DG sets:
- F. **PLC /Relay Based: 25 KVA**
- G. S/F of DG Set Exhaust Piping insulation on 80 mm to 150 mm Dia. MS Exhaust Pipe as per CPCB-2 norms.
- H. Rock /Glass wool with 22 g Aluminium cladding (Density- 96 kg/m3, Thickness-50 mm)
- I. Construction of Platform of Size 3600 x 1800 x 600 mm including earth work ,150 mm thick concreting under masonry wall and C.C. floor , mm thick masonry wall as required as per site condition and 75 mm thick C.C. floor, outer face of wall should be finished with 20 mm th cement plaster complete with all respect
- J. Plate Earthing as per IS:3043 with copper Earth plate of size 600mm x 600mm x 3.0mm by embodying 3 to 4 mtr. below the ground level w 25 mm dia. G.I. 'B' class watering Pipe including all accessories like nut, bolts, reducer, nipple, wire meshed Funnel, and C.C. finished chamf




All wiring should be in copper except specified.

1. Connection with the existing electrical panel shall be done by the Firm.
 2. For which test certificate shall be produced from govt. approved agency.
 3. Bidder should Quote rates including installation work in all respect
 4. The firm should submit valid type of approved certificate with authorization from CP/CRPCB following are the mandatory required certification
 - (i) Type of approval/COP data for emission compliance of diesel generator from ARAI/CAT/VRDE.
 - (ii) Type of approval/COP data for noise compliance of diesel generator from FCRI/ARAI/NAL/CAT.
 5. Onsite maintenance of the whole work/product shall be 5 years from Completion of guarantee (CMC)
 6. Complete work shall be carried out by the manufacturer.
 7. Guarantee shall be given by principal manufacturer/authorized dealer/executing agency of the product and allied installation work for the period 2 years from the date of installation. Bidder should mention guarantee / Service provider.
 8. **Comprehensive Maintenance Service:** CMC will be given @ 3 % of net rate excluding GST (as applicable) and yearly escalation of 5 % on last year's CMC price. The CMC may be awarded for five years (on yearly basis) after Guarantee period of two years.
 9. During Guarantee and onsite maintenance period consumables like all kind of filters, Engine oil, coolant , fan belt, washers, diesel, distilled water for batteries and hose pipes will be provided by the department as and when required also quarterly inspection and two services/year will be provided by the manufacturer free of cost.
- Pre-Dispatch and Post Installation Inspection will be done by nominated Committee

Rates of Consumables/Accessories (In Rs.) :-

S.no	Name of Item	Brand/Model	Approved Rate (Per Meter)
1	50.0 sq.mm 4core(armoured) Cable	Mahindra Powerol	302 + IGST @ 18%
2.	Exhaust Pipe	Mahindra Powerol	1224 + IGST @ 18%


 Executive Director (EPM)
 Rajasthan Medical Services Corporation Ltd.,
 Jaipur

No. F-8(110) RMSC/EPM/M-4/2017-18/NIB-322/

Copy forwarded to the following for information & necessary action:

P.S. to Mission Director NHM Jaipur.

1. Director, (PH)/(Aids)/(RCH)/(ECY)/(ESD), Principal, Medical College, Ajmer, Bikaner, Jaipur, Jodhpur, Kota, Jhalawar & Udaipur.
2. Superintendent Jaipurya Hospital Jaipur (Associated with RUHS College of Medical Sciences, Jaipur).
3. Director, Medical & Health Services (ESD), Mobile Surgical Unit, Raj. Jaipur.
4. All P.M.O.'s.
5. All CM&HO's.
6. Executive Director (Logistics/Finance)
7. AGM (IT), RMSC, Jaipur
8. All DPC's DDW Rajasthan.
9. M/s Tanwar Industries, Jalupura Link Road, M. I. Road Jaipur Email: info@tanwarindustries.com
10. Guard file.

Dated:


Executive Director (EPMJ)

Rajasthan Medical Services Corporation Ltd.,
Jaipur